

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 30 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 1-30-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Intent to Drill,
 filed January 16, 1968

Dear Sir:

Mr. Gerd Steincamp of Strata Drilling, Inc. has this
 date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Strata Drilling, Inc.

Complete Address: P. O. Box 355, Great Bend, Kansas 67530

Lease Name: Commercial Jones Well No. # 1

Location: C SW NW Sec. 7 Twp. 27 Rge. 14 (E)(W) W

County Pratt Total Depth 4625' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

324' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill
hole with drilling mud to 275', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge rat & mouse holes and cement with 4 sacks

Very truly yours,

Archie Elving
 Conservation Division Agent