

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water),
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
CONSERVATION DIVISION

AUG 21 1967

8-21-67

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed July 5, 1967.

Dear Sir:

Mr. Howard Cain of Peel Brothers, Inc. has this
date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Amarillo Natural Gas Company

Complete Address: 305 Bank of Southwest, Amarillo, Texas

Lease Name: Jones Well No. # 1

Location: 440' N of SL and
440' E of WL SE Sec. 7 Twp. 27 Rge. 14 (E)(W) W

County Pratt Total Depth 4684' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cain was instructed to plug the well as follows:

336' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fill
hole with drilling mud to 250', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving
Conservation Division Agent