

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Clyde Merckle of Lauck Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Merckle guarantees payment of the plugging fee.

Operator's full Name: Richard L. Bohanon

Complete Address: 1617 Bedford Drive, Oklahoma City, Oklahoma

Lease Name: Montford Well No. # 1

Location: C SE SW Sec. 26 Twp. 27 Rge. 13 (E) (W) W

County Pratt Total Depth 4475 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Merckle was instructed to plug the well as follows:

303' of 8 5/8" surface pipe, cement circulated with 220 sacks.
Fill hole with drilling mud to 300', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving