

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 8 1973  
1-8-73  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Oden of Red Tiger Drlg Co has this

date requested permission to plug the following described well:

Mr. Oden guarantees payment of the plugging fee.

Operator's full Name: Tatlock Oil Co

Complete Address: 1313 Union Natl Bldg Wichita, KS

Lease Name: Jones Well No. 1

Location: A/C SW/SE Sec. 6 Twp. 27s Rge. 14 (E)(W)W

County: Pratt Total Depth 4601 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Oden was instructed to plug the well as follows:

448 ft 8 5/8 surface pipe cemented with 500 sacks. Pump  
40 sacks cement to 435 ft. Mud to 40 ft, plug, 1/2 sack  
hulls, 15 sacks cement to surface. 2 sacks cement in  
rat hole.

Pumped by Halliburton Cementing Co Great Bend, KS

Very truly yours,

Russell B. Binkley  
Conservation Division Agent