

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-01506-00-02  
Spot: SESENESW Sec/Twnshp/Rge: 12-9S-17W  
1646 feet from S Section Line, 2965 feet from E Section Line  
Lease Name: MCCLAY Well #: 6  
County: ROOKS Total Vertical Depth: 3700 feet

Operator License No.: 6627  
Op Name: PROSPECT OIL & GAS CORP  
Address: PO BOX 837  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3588		175 SX
SURF	8.62	218		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2014 11:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: BRAD HUTCHISON Company: PROSPECT OIL & GAS CORP. Phone: (785) 483-6266

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 200 # hulls, 13 sx gel and 50 sx common 3% c.c..  
DV Tool at 1453' w/500 sx cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/11/2014 4:40 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3352' and pumped 13 sx gel followed by 75 sx cement w/200 # hulls. Pulled tubing to 1883' and pumped 50 sx common 3% c.c. Pulled 800' tubing to 1183'. Ran tubing to tag plug at 1890'. Pulled tubing to 1850' and pumped 150 sx cement to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing w/15 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pressured up immediately.

GPS: 39.28248N -099.16882W

Perfs:

Remarks: QUALITY OILWELL CEMENTING TICKET # 6316

Plugged through: TBG

12/31/CM

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)  
Received  
KANSAS CORPORATION COMMISSION

CM

DEC 13 2014

DEC 24 2014

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS