

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23634-00-01
Spot: NESESENE Sec/Twnshp/Rge: 25-16S-22W
2984 feet from S Section Line, 326 feet from E Section Line
Lease Name: LINDEN Well #: 5
County: NESS Total Vertical Depth: 4392 feet

Operator License No.: 31086
Op Name: RICHLAN DRILLING, A GENERAL PAR
Address: 598 2ND AVE
BEAVER, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4205		WITH 2 SX CMT
PROD	5.5	4384	0	
SURF	8.625	331		WITH 190 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/09/2014 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: RICK SCHREIBER Company: RICHLAN DRILLING Phone: (620) 793-2032

Proposed Plugging Method: SET CIBP @ 4215' WITH 2 SX CMT. SQUEEZE PERFS WITH 25 SX CMT & 150# HULLS. RUN BOND LOG TO 1750'.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 12/09/2014 3:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 4205' WITH 2 SX CMT. RUN BOND LOG & FOUND CMT FROM 1650'-260'. SWABBED TO 1700' & PUMPED 175 SX CMT. PRESSURED TO 450#. WENT DOWN BACKSIDE WITH 25 SX CMT. PRESSURED TO 350# & HELD.

Perfs:

Top	Bot	Thru	Comments
4266	4267		
4265	4266		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

12/31/14 CKM

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
DEC 17 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
DEC 24 2014
CONSERVATION DIVISION
WICHITA, KS