

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-057-20765-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 18-27S-22W  
2376 feet from S Section Line, 960 feet from W Section Line  
Lease Name: HENRY 18BC Well #: 1  
County: FORD Total Vertical Depth: 5315 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1445		CEMENTED WITH 335 SX CMT. 20 SX CMT CIRCULATED TO PIT.
PROD	5.5	5300	0	WITH 175 SX CMT
SURF	8.625	351		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/17/2014 11:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0330

Proposed Plugging Method: PLUG PERFS WITH 75 SX CMT & 200# HULLS. GEL SPACER TO ANHYDRITE. CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/17/2014 12:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

BULLHEADED 75 SX CMT WITH 200# HULLS, 60 BBL MUD SPACER TO APP. 1600' & CMT TO SURFACE WITH 80 SX CMT. PRESSURED TO 500#. BACKSIDE HAD CMT BEHIND THE BULLPLUG.

Perfs:

Top	Bot	Thru	Comments
4992	4996		
4991	4995		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

12/31/14 CKM

District: 01

RECEIVED  
DEC 22 2014  
KCC DODGE CITY

Signed Eric MacLaren

(TECHNICIAN)  
Received  
KANSAS CORPORATION COMMISSION

DEC 24 2014

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3