

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21787-00-00
Spot: NWSENW Sec/Twnshp/Rge: 1-21S-18W
1500 feet from N Section Line, 1500 feet from W Section Line
Lease Name: WEISENSEE 1B Well #: 1
County: PAWNEE Total Vertical Depth: 4250 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1173		WITH 575 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/26/2014 11:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: BILL SANDERS Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: 1ST PLUG AT 3925' WITH 50 SX CMT. 2ND PLUG AT 1200' WITH 50 SX CMT. 3RD PLUG AT 480' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: NONE
Date/Time Plugging Completed: 10/26/2014 1:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

1ST PLUG AT 3925' WITH 50 SX CMT. 2ND PLUG AT 1200' WITH 50 SX CMT. 3RD PLUG AT 480' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

12/31/14 cfm

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
DEC 23 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

DEC 24 2014
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3