

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21308-00-00
Spot: NWSESE Sec/Twnshp/Rge: 33-30S-17W
1270 feet from S Section Line, 957 feet from E Section Line
Lease Name: WEDEL LUCKY Well #: 7
County: KIOWA Total Vertical Depth: 5679 feet

Operator License No.: 32781
Op Name: ROBERTS RESOURCES, INC.
Address: 2020 N TYLER RD, STE 106
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4960		WITH 2 SX CMT
PROD	4.5	5677	1402	WITH 135 SX CMT
SURF	8.625	422		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2014 9:00 AM
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC
Proposal Rcvd. from: KENT ROBERTS Company: ROBERTS RESOURCES Phone: (316)215-1683

Proposed Plugging Method: SET CIBP @ 4978' WITH 2 SX CMT. PLUG AT 1080' WITH 15 SX GEL & 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2014 12:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 4960' WITH 2 SX CMT. 1ST PLUG AT 1114' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 448' WITH 50 SX CMT. 3RD PLUG AT 74' WITH 20 SX CMT. CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5316	5326		
5028	5062		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

12.31.14 CKM

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
DEC 22 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
DEC 24 2014
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3