

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-21094-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 33-9S-23W  
715 feet from S Section Line, 1025 feet from E Section Line  
Lease Name: RICE ESTATE Well #: 2  
County: GRAHAM Total Vertical Depth: 4000 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 211 S FRONT ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4000		150 SX
SURF	8.625	200		160 SX

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/19/2014 10:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JEREMY ULRICH Company: SCHECK OIL OPERATION Phone: (785) 483-0395

Proposed Production perforations: 3784' - 3787'.  
Plugging CIBP at 3805'  
Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/19/2014 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each at 2550', 1920', 1253' and 190'. Ran tubing to 3500'. Quality pumped 150 sx cement w/300 # hulls. Pulled tubing to 1700' and pumped 125 sx cement w/200 # hulls. Cement circulated. PTOH. Pumped 45 sx cement down 4 1/2" casing and circulated cement out 8 5/8" surface casing.

Perfs:

Top	Bot	Thru	Comments
3922	3924		
3903	3909		
3820	3824		
3784	3787		

Remarks: QUALITY

Plugged through: TBG

12-31-14 CKM

District: 04

Signed Richard Williams

(TECHNICIAN)

CM

KCC WICHITA

DEC 22 2014

DEC 30 2014

Form CP-2/3

RECEIVED