

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-20944-00-00
Spot: SESWNE Sec/Twnshp/Rge: 28-14S-13W
2310 feet from N Section Line, 1650 feet from E Section Line
Lease Name: GIESE Well #: 16
County: RUSSELL Total Vertical Depth: 2400 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC.
Address: 326 N MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.125	2397		100 SX
SURF	8.587	238		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2014 9:00 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: MIKE MCGLOCKLIN Company: SHIELDS OIL PRODUCERS Phone: (785) 483-9800

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/15/2014 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 350', 650', 1350'. Ran tubing to 2350' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1300' and pumped 100 sx cement w/100 # hulls. Cement circulated out the back side. POOH. Hooked to casing and pumped 120 sx cement. Cement circulated out the braden head. Shut in.

GPS: 38.80670 -098.76859

Perfs:

Remarks: ALLIED CEMENTING TICKET # 0556011

Plugged through: TBG

12-31-14 CKM

District: 04

Signed

Ray Dinkel

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

CM

DEC 16 2014

DEC 24 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3