

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19363-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 11-25S-3E
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: DOHERN A Well #: 10
County: BUTLER Total Vertical Depth: 2731 feet

Operator License No.: 34569
Op Name: SONOMA RESOURCES LLC
Address: PO BOX 384
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2718	264	35 SX
SURF	12.5	90		125 SX
T1	2.825	2600	264	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2014 8:00 AM
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC
Proposal Rcvd. from: DAN FLOWERS Company: SONOMA RESOURCES Phone: (316) 208-7590

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 12/12/2014 5:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) PULLED 3 JTS OF 2.825" TUBING AND LEFT REMAINING IN HOLE DUE TO PARTED 5.5" PRODUCTION CASING AND SHOT AT APPROX. 2580' (WIRELINE WAS UNABLE TO GO FURTHER DOWN). 2.) PUMPED 35 SXS CLASS A CEMENT W/ 3% CACL AND 05. LB/SK FLO-SEAL DOWN TUBING AND SHUT IN OVERNIGHT TO SET. 3.) TAGGED ON BOTTOM PLUG ON 12/12/14 WITH WIRELINE AT APPROX. 1771'. 4.) SHOT OFF TUBING AND CASING AT APPROX. 264' AND SPOTTED 100 SXS OF CEMENT. 5.) PULL BOTH CASING AND TUBING OUT OF HOLE (5.5 CASING WAS VERY DETERIORATED AND CAME OUT OF HOLE WITH WHEN TUBING WAS PULLED). 6.) TAGGED ON CEMENT AT APPROX. 135' AND THEN PUMPED 100 SXS CEMENT AND CIRCUALTED CEMENT TO SURFACE. 7.) ON 12/15/14, KCC TAGGED ON CEMENT AT APPROX. 2' BELOW SURFACE.

Perfs:

Top	Bot	Thru	Comments
2700	2731	OH	

Remarks: CONSOLIDATED WELL SERVICES COMPELTED CEMENT WORK. TICKET # FOR BOTTOM PLUG: 48514. TICKET #FOR TOP PLUG: 48523. TA NOV

Plugged through: TBG

12.31.14 CKM

District: 02

Signed Jonathan Hill

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 24 2014

CONSERVATION DIVISION
WICHITA, KS

JK