

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-21711-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 21-9S-24W
4966 feet from S Section Line, 2206 feet from E Section Line
Lease Name: HURLBUT Well #: 1
County: GRAHAM Total Vertical Depth: 4088 feet

Operator License No.: 34392
Op Name: TEXKAN EXPLORATION LLC
Address: 307 NW 3RD ST PO BOX H
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4088		150 SX
SURF	8.625	253		253 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/10/2014 10:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TOM BERENS Company: TEXKAN EXPLORATION LLC Phone: (785) 688-4040

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Production perforations: 3892' - 3896'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/10/2014 2:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 2150', 1050' and 2600'. Ran tubing to 3808' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 2580' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1117' and pumped 125 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/25 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 50 sx cement. Maximum pressure 75 psi.

GPS: 39.26156N -100.00358W

Perfs:

Remarks: ALLIED TICKET # 55401

Plugged through: TBG

12-31-14 CKM

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

CM

DEC 19 2014

DEC 24 2014

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS