

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-023-20080-00-00  
Spot: NENW Sec/Twnshp/Rge: 25-4S-37W  
660 feet from N Section Line, 1980 feet from W Section Line  
Lease Name: JENSEN Well #: 1  
County: CHEYENNE Total Vertical Depth: 4771 feet

Operator License No.: 31514  
Op Name: THOROUGHbred ASSOCIATES L.L.C.  
Address: 8100 E 22ND ST STE 600  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4759		200 SX
SURF	8.625	390		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/12/2014 12:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: BOBBY PATTON Company: THOROUGHbred ASSOCIATES Phone: (316) 685-1512

Proposed Plugging Method: 8 5/8" surface casing set at 390' w/250 sx cement. 4 1/2" production casing set at 4759' w/200 sx cement. TD 4771'. PBTD 4728'. Perforations: 4612' - 4649'. Casing in poor condition.  
Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/12/2014 7:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Rigged up power swivel and mud pump. Drilled 4 1/2" production casing to 3966'. Encountered hard spot at 3975'. KCC district 4 supervisor approved plugging from 3975'. Perforated production casing at 3107', 2362' and 370'. Ran tubing to 3966' and pumped 110 sx cement w/300 # hulls. Pulled tubing to 3000' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 1500' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 370' and pumped 140 sx cement. Cement circulated to surface from 8 5/8" surface casing and 4 1/2" production casing. Pulled tubing to surface and topped off w/25 sx cement.

GPS: 39.68268N -101.42310W

Perfs:

Top	Bot	Thru	Comments
4647	4649		
4622	4626		
4612	4649		

Remarks: BASIC ENERGY SERVICES TICKET # 5096

Plugged through: TBG

12/31/14 CKM

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CR

DEC 22 2014

KCC WIC Form CP-2/3

DEC 30 2014

RECEIVED