

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-20081-00-00
Spot: SWSE Sec/Twnshp/Rge: 24-4S-37W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: JENSEN Well #: 2
County: CHEYENNE Total Vertical Depth: 4755 feet

Operator License No.: 31514
Op Name: THOROUGHBRED ASSOCIATES L.L.C.
Address: 8100 E 22ND ST STE 600
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4754		200 SX
SURF	8.625	405		315 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/16/2014 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: BOBBY PATTON Company: THOROUGHBRED ASSOCIATES Phone: (316) 685-1512

Proposed Plugging Method: 8 5/8" surface casing set at 405' w/315 sx cement. 4 1/2" production casing set at 4754' w/200 sx cement. TD 4755'. Perforations: 4687' - 4746'. Casing condition is poor.
Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2014 7:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran casing swab with jars to 4700'. Pulled to surface. Perforating gun could not get below 2806'. Ran rock bit on tubing to 2806'. Milled to 2950'. Circulated iron sulfide and metal chips to surface. District 4 supervisor advised to plug from 2950' due to poor casing condition. Tubing to surface. Perforated production casing at 2375' and 375'. Ran tubing to 2950' and pumped 110 sx cement w/300 # hulls. Pulled tubing to 1500' and pumped 75 sx cement w/150 # hulls. Pulled tubing to 389' and pumped 180 sx cement. Circulated cement from 8 5/8" surface casing and 4 1/2" production casing. Pulled tubing to surface. Topped casing w/80 sx cement.

GPS: 39.68625N -101.41837W

Perfs:

Top	Bot	Thru	Comments
4744	4746		
4711	4713		
4694	4700		
4687	4746		

Remarks: BASIC ENERGY SERVICES TICKET # 11,756 (PRATT CAMP)

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

12/31/14 ckm

CM

DEC 19 2014

KCC WICHITA Form CP-2/3

DEC 30 2014

RECEIVED