

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-21119-00-00
Spot: SWNESWNW Sec/Twnshp/Rge: 17-17S-33W
1675 feet from N Section Line, 952 feet from W Section Line
Lease Name: CJK Well #: 1-17
County: SCOTT Total Vertical Depth: 4800 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	242		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/20/2014 5:30 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: ANGEL Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 2450' WITH 50 SX CMT. 2ND PLUG AT 1450' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT., 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 12/20/2014 7:25 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG AT 2450' WITH 50 SX CMT. 2ND PLUG AT 1450' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT., 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed


(TECHNICIAN)

12/31/14 CKM

RECEIVED
DEC 22 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

DEC 24 2014
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3