

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-24086-00-00
Spot: SESWNENE Sec/Twnshp/Rge: 30-8S-23W
1050 feet from N Section Line, 800 feet from E Section Line
Lease Name: BILLIPS Well #: 1-30
County: GRAHAM Total Vertical Depth: 3960 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2255 S WADSWORTH, STE 205
LAKEWOOD, CO 80227

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	262		160 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/07/2014 12:00 AM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: JOHN Company: AMERICAN EAGLE DRILLING LLC Phone: (785) 302-0476

Proposed Plugging Method: Ordered 240sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: NONE
Date/Time Plugging Completed: 12/07/2014 1:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report: _____ Perfs: _____

1st plug @2050 w/50 sx
2nd plug @1200 w/100 sx
3rd plug @320 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx

Remarks: QUALITY
Plugged through: DP

12/31/14 CKM

District: 04

Signed Darrel Dipman

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

CM

DEC 11 2014

DEC 24 2014

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS