

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23485-00-00
Spot: N2SWSW Sec/Twnshp/Rge: 10-18S-26W
1041 feet from S Section Line, 4537 feet from E Section Line
Lease Name: SHERWIN TRUST Well #: 2-10
County: NESS Total Vertical Depth: 4525 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	4260		WITH 20 SX CMT
PC	4.5	1915		WITH 375 SX CMT
PROD	4.5	4522	0	WITH 190 SX CMT
SURF	8.625	216		WITH 145 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2014 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE RUPP Company: VESS OIL Phone: (785) 798-5151

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS WITH CMT. PULL TBG TO ANHYDRITE & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/04/2014 5:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4260'. RUN TBG TO 4234' & SPOT 20 SX CMT. PULL TBG TO 1800' & PUMPED 50 SX CMT & 300# HULLS. WENT ON VACUUM. PULLED TBG TO 1500' & WAITED 1 HOUR. PUMP 120 SX CMT & 300# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4435	4442		
4317	4321		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

12/31/14 CKM

District: 01

RECEIVED
DEC 17 2014
KCC DODGE CITY

Signed Michael Maier
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

DEC 24 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3