

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-24089-00-00
Spot: NWSESENE Sec/Twnshp/Rge: 3-7S-22W
2170 feet from N Section Line, 435 feet from E Section Line
Lease Name: WORCESTER Well #: 3-3
County: GRAHAM Total Vertical Depth: 3754 feet

Operator License No.: 30259
Op Name: WERTH, ANDY DBA WERTH EXPLORA
Address: 1308 SCHWALLER AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	215		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/15/2014 12:00 AM
Plug Co. License No.: 34908 Plug Co. Name: SKYTOP DRILLING LLC
Proposal Rcvd. from: TOM Company: SKYTOP DRILLING LLC Phone: (785) 259-2002

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY WitnessType: NONE
Date/Time Plugging Completed: 12/15/2014 7:00 PM KCC Agent: CHRIS NEELEY

Actual Plugging Report:

1st plug @1900 w/50 sx
2nd plug @1090 w/100 sx
3rd plug @280 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

District: 04

Signed

Chris Neeley

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

DEC 24 2014

CONSERVATION DIVISION
WICHITA, KS

12/31/14 CKM