

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-23550-01-00  
Spot: SWSESWNE Sec/Twnshp/Rge: 20-34S-11W  
2376 feet from N Section Line, 1794 feet from E Section Line  
Lease Name: SUMMERS A Well #: 5H  
County: BARBER Total Vertical Depth: 4660 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3680		WITH 20 SX CMT
COND	20	40		WITH 150 SX CMT
	I1 7	5023	1050	30 sxs 60/40 poz
PROD	4.5	7794	3508	365 SX
SURF	13.375	239		300 SX

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/17/2014 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: BILL GALLAGHER Company: WOOLSEY OPERATING Phone: (620) 886-0093

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/17/2014 3:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3680' & SPOT 20 SX CMT THROUGH TBG ON TOP OF CIBP. CUT & LAY DOWN RECOVERABLE 4 1/2" & 7" CASING. 1ST PLUG AT 612' WITH 20 SX GEL & 75 SX CMT. 2ND PLUG AT 276' WITH 100 SX CMT. 3RD PLUG AT 42' WITH 45 SX CMT.

7800  
- 4660  
-----  
3140

Perfs:

Top	Bot	Thru	Comments
6186	7726		OA
5913	6115		
5644	5846		
5370	5572		
5098	7726		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE. TMD = 7800'.

Plugged through: CSG

12/31/14 cfm

District: 01

RECEIVED  
DEC 22 2014  
KCC DODGE CITY

Signed

*Stephen J. Pfeifer*  
Received (TECHNICIAN)  
KANSAS CORPORATION COMMISSION

DEC 24 2014

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3