

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 10 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of Graves Drilling Co. has this
 date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Ferguson Oil Co.

Complete Address: 522 Union Center Bldg., Wichita, Kansas

Lease Name: Peters Well No. # 1

Location: C SE NE Sec. 22 Twp. 27 Rge. 14 (E) (W) W

County Pratt Total Depth 4665 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

424' of 8 5/8" surface pipe, cement circulated with 500
Sacks. Fill hole with mud to 240', 1st cementing plug,
1/4 sack hulls, cement with 20 sacks. Fill hole with mud
to 40', 2nd cementing plug, 1/4 sack hulls, cement with
10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent