

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 18 1963  
11-18-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Wilcox Oil Co.

Complete Address: Box 1440, Tulsa, Oklahoma

Lease Name Vernon Well No. # 1

Location NE SW NW Sec. 28 Twp. 27 Rge. 13 (E) (W)W

County Pratt Total Depth 4550

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Jones-Gebbert Oil Co.

Address: 205 Central Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 11:30AM Day 17th Month Nov. Year 1963

The Above well was plugged as follows:

418' of 8 5/8" surface pipe, cemented with 275 sacks. Hole was filled  
with drilling mud to 300', 1st cementing plug, bridged with 1/2 sack hulls,  
cemented with 25 sacks. Hole was filled with drilling mud to 40', 2nd  
cementing plug, bridged with 1/2 sack hulls, cemented with 10 sacks to  
base cellar. Rat hole bridged and cemented with 5 sacks.

The cementing of the plugs was done by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 11/19/63  
INV. NO. 8128-W

Signed: Archie Elving  
Well Plugging Supervisor