

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 2 1970
CONSERVATION DIVISION
Wichita, Kansas
2-2-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name U. S. Hydrocarbon Co.

Complete Address Box 11027 Wichita, Ks 67218

Lease Name Jones A Well No. 2

Location C/SW Sec. 7 Twp. 27 Rge. 14 (E) (W) W

County Pratt Total Depth 4250

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks License No. 624

Operation Completed: Hour 4-30 PM Day 30 Month I Year 1970

The above well was plugged as follows:

323 ft. of 8 5/8 surface pipe circulated with cement. 4248 ft. of
4 1/2 long string set with 150 sacks cement. 3430 ft of 4 1/2 pulled.
4 sacks cement with bailer, 10 ft. rock bridge, plug, 25 sacks cemented
at 300 ft. Mud to 40 ft. 10 ft. rock bridge, plug, 10 sacks cement
to top of surface..

I hereby certify that the above well was plugged as herein stated.

Signed: Russell B. Bherntem
Well Plugging Supervisor

INVOICED

DATE 2/2/70

INV. NO. 1344-W