

JP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed January 16, 1968

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1968
CONSERVATION DIVISION
Wichita, Kansas
1-30-68

Operator's Full Name Strata Drilling, Inc.

Complete Address: P. O. Box 355, Great Bend, Kansas 67530

Lease Name Commercial Jones Well No. # 1

Location C SW NW Sec. 7 Twp. 27 Rge. 14 (E) (W)

County Pratt Total Depth 4625'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Strata Drilling, Inc.

Address: P. O. Box 355, Great Bend, Kansas 67530 License No.

Operation Completed: Hour 10:30AM Day 29th Month January Year 1968

The Above well was plugged as follows:

324' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid level
in the hole was at 120'. 1st cementing plug and 1 sack of hulls was pushed
in fluid to 275', and cemented with 25 sacks, through the drill pipe, with
cement from 275' to 200'. Hole was filled with drilling mud to 40', 2nd
cementing plug, bridged with 1 sack of dry cement and 1/2 sack of huls on
fluid at 40', and cemented with 9 sacks, with cement from 30' to the base
of the cellar. Rat and mouse holes bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1/30/68
INV. NO. 9178-W

Signed: Archie Elving
Well Plugging Supervisor