

69

Form CP-3
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 1967
8-21-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed July 5, 1967.

Operator's Full Name Amarillo Natural Gas Company

Complete Address 350 Bank of Southwest, Amarillo, Texas.

Lease Name Jones Well No. # 1

Location 440' N of SL and 440' E of WL SE SW-SWSE Sec. 7 Twp. 27 Rge. 14 (E) (W) W

County Pratt Total Depth 4684'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Peel Brothers, Inc.

Address BOX 359, Hoisington, Kansas License No.

Operation Completed: Hour 9:00 P.M. Day 16th Month August Year 1967

The above well was plugged as follows:

336' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid level in the hole was at 135'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 250', and cemented with 35 sacks, through the drill pipe, with cement from 250' to 145'. Hole was filled with drilling mud to 40', bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and cemented with 9 sacks, with cement from 30' to the base of the cellar. Rat hole bridged and cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8-22-67
INV. NO. 6172-W