

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 10-5-

LOCATION SW-NW-SE

SEC 24 TWP 27 RGE. 13W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease John J Helmske

Operator Stam Lind Oil - Gas Co Address Ellenwood Kansas

Field _____ County Pratt

Total Depth 4460 Feet.

Plugging Contractor West Supply Co (Ralph)

Plugging Contractor's License No. 14

Address Chase Kansas.

(Describe briefly the manner in which the well was plugged)

8 1/2" 6 8/16" Circulated With Cement
5 1/2" 4459' Cemented with 100# cement drilled
out to 4379' Perforated 4349' to 4353' hole
filled with sand to 4335' run 5# cement
with check valve. Pulled 5 1/2" 3800'
hole filled with Mud to 300' set sock
bridge run 20# cement Mud to 35' set
sock bridge run 10# cement cap.

PLUGGING
FILE SEC 24 TWP 27 R 13W
BOOK PAGE 10 LINE 5

02-08-54

M. L. Riess
District Conservation Agent

Date 2-7-54