

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20800-00-00
Spot: E2SESWNW Sec/Twnshp/Rge: 14-22S-40W
2952 feet from S Section Line, 4010 feet from E Section Line
Lease Name: ENGELLAND Well #: 3-14
County: HAMILTON Total Vertical Depth: 2954 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2952	0	WITH 700 SX CMT
SURF	8.625	359		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/20/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 200 SX CMT WITH 250# HULLS. USE 50 SX CMT FOR ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/20/2014 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2764' TO 0' USING 150 SX CMT WITH 250# HULLS. PRESSURE TO 500#. HOLDING. PUMP 5 SX CMT DOWN THE ANNULUS TO 250#. TOP OFF 4 1/2" CASING WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2746	2764		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

Ken Jehlik 12/17/2014 com
(TECHNICIAN)

RECEIVED

DEC - 2 2014

KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

DEC 11 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3