

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-081-21193-00-00  
Spot: SWSW Sec/Twnshp/Rge: 27-29S-34W  
702 feet from S Section Line, 641 feet from W Section Line  
Lease Name: MLP FOSTER Well #: 1-27  
County: HASKELL Total Vertical Depth: 5547 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5250		WITH 2 SX CMT
PC	5.5	3042		NEVER CEMENTED
PROD	5.5	5540	1800	WITH 150 SX CMT
SURF	8.625	1767		WITH 650 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/25/2014 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 5260' WITH 2 SX CMT. PLUG AT 1800' WITH 20 SX GEL & 50 SX CMT. PLUG AT 700' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/25/2014 12:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5250' WITH 2 SX CMT. 1ST PLUG AT 1794' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 706' WITH 40 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5308	5404		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
DEC - 4 2014  
KCC DODGE CITY

Signed \_\_\_\_\_

*Kenny Sullivan*

Received  
KANSAS CORPORATION COMMISSION

DEC 11 2014

CONSERVATION DIVISION  
WICHITA, KS

12/17/14 CKM

*51*