

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-093-20418-00-00
Spot: SW Sec/Twnshp/Rge: 28-22S-37W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: FINN Well #: 1-28
County: KEARNY Total Vertical Depth: 3050 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1000		
PROD	5.5	3041	0	WITH 300 SX CMT
RBP		2743		WITH 2 SX CMT
SURF	8.625	310		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/19/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2014 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

RBP @ 2743' WITH 2 SX CMT. PUMP 40 SX CMT AT 2105' TO 1700' THROUGH TBG. FULL CIRCULATION. SET CIBP @ 1000'. LOAD & TEST CASING TO 600#. HOLDING. RUN BOND LOG FROM 1000' TO 10'. NO CMT BEHIND CASING. PERFORATED 4 HOLES AT 970'. PUMP 40 SX CMT, 50# HULLS THEN 40 SX CMT DOWN 5 1/2" CASING. DISPLACE CMT TO 536' @ 1000# LEAVING 40 SX CMT INSIDE THE CASING & 40 SX CMT OUTSIDE THE CASING. PERFORATE 4 HOLES AT 350'. CIRCULATE CMT TO SURFACE THROUGH PERFS WITH 100 SX CMT. TOP OUT WTH 10 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2800	2896		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

RECEIVED
DEC - 3 2014
KCC DODGE CITY

Signed Ken Jehlik (TECHNICIAN)
KCC WICHITA
DEC 12 2014
RECEIVED

12/17/14 CKM