

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-20613-00-01  
Spot: SWNW Sec/Twnshp/Rge: 28-21S-21W  
1943 feet from N Section Line, 660 feet from W Section Line  
Lease Name: STEFFEN OWWO Well #: 1  
County: HODGEMAN Total Vertical Depth: 4500 feet

Operator License No.: 33235  
Op Name: CHIEFTAIN OIL CO., INC.  
Address: 101 S. 5TH ST. PO BOX 124  
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4495	0	WITH 450 SX CMT
SURF	8.625	216		WITH 150 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/01/2014 9:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: ROB RALEIGH Company: CHIEFTAN OIL Phone: (620) 825-4030

Proposed Plugging Method: BULLHEAD 30 SX CMT WITH 200# HULLS THROUGH PERFS. MUD SPACER TO 1310'. CMT TO SURFACE. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/01/2014 1:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

BULLHEAD 30 SX CMT WITH 200# HULLS THROUGH PERFS. DISPLACED TO 1310' WITH 68 BBL MUD SPACER. CMT TO SURFACE WITH 180 SX CMT. CHECK BACKSIDE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4349	4352		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

12/17/14 CKM

District: 01

Signed Larry Harris  
(TECHNICIAN)

RECEIVED  
DEC - 5 2014  
KCC DODGE CITY

KCC WICHITA  
DEC 12 2014  
RECEIVED

[Signature]