

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-26704-00-01
Spot: NENENENE Sec/Twnshp/Rge: 23-25S-19E
5060 feet from S Section Line, 220 feet from E Section Line
Lease Name: KNOX Well #: 26
County: ALLEN Total Vertical Depth: 890 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	887		130 SX
SURF	6.25	20		4 SX

Well Type: EOR UIC Docket No: E10334.105 Date/Time to Plug: 09/26/2014 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: RICK RICE Company: Phone: (620) 365-3111

Proposed Plugging Method: COMPANY SERVICE UNIT RIH 1" TBG TO BTM SERVICE COMPANY PUMP CEMENT TO SURFACE.
COMPANY SERVICE UNIT PULL 1" TBG OUT. SERVICE COMPANY HOOK ON TO 2 7/8" TBG PRESSURE UP
WELL SHUT IN. COME BACK LATER CUT SURFACE OFF "BELOW FLOW DEPTH"

Plugging Proposal Received By: WitnessType: NONE
Date/Time Plugging Completed: 09/26/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Hooked onto the 2.875" casing and squeezed cement through the 2.875" casing from surface to TD. Shut well in with 400 psi. A total of 25 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
840	864		
784	794		

RECEIVED

DEC 10 2014

KCC Chanute Dist #3

RD

Remarks:

Plugged through: TBG

District: 03

Signed

cc: UIC

(TECHNICIAN)

12/17/14 ckm

KCC WICHITA

Form CP-2/3

DEC 12 2014

RECEIVED