

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-19144-00-00
Spot: S2NWSE Sec/Twnshp/Rge: 14-22S-12W
1649 feet from S Section Line, 1888 feet from E Section Line
Lease Name: HALLMAN A Well #: 1
County: STAFFORD Total Vertical Depth: 3665 feet

Operator License No.: 4656
Op Name: DAVIS PETROLEUM, INC.
Address: 7 SW 26 AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3280		WITH 2 SX CMT
PROD	5.5	3664	0	WITH 110 SX CMT
SURF	8.625	242		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2014 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 3280' & 2 SX CMT. PLUG AT 620' WITH 200 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/13/2014 2:00 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 3280' WITH 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE AT 620'. 1ST PLUG AT 620' WITH 200 SX CMT. DID NOT CIRCULATE, RAN OUT OF CMT. WAIT 2 HOURS & TAG TOP OF CMT WITH SANDLINE. TOC @ 300'. PUMP 50 SX CMT THROUGH SURFACE PIPE TO TOP OF PRODUCTION CASING. DID CIRCULATE TO TOP OF PRODUCTION CASING.

Perfs:

Top	Bot	Thru	Comments
3494	3496		
3472	3474		
3436	3442		
3358	3360		
3348	3350		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

12/17/2014 cpm

District: 01

Signed

Robert Dickerson

(TECHNICIAN)

RECEIVED

DEC - 5 2014

KCC DODGE CITY

ST

Form CP-2/3