

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-10058-00-00  
Spot: NESW Sec/Twnshp/Rge: 16-21S-41W  
1954 feet from S Section Line, 3298 feet from E Section Line  
Lease Name: HCU Well #: 1611  
County: HAMILTON Total Vertical Depth: 2770 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2692		
PROD	4.5	2768	0	WITH 100 SX CMT
SURF	8.625	113		WITH 75 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/04/2014 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: GILBERTO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/04/2014 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2692'. PUMP 35 SX CMT FROM 2661' TO 2181'. RUN BOND LOG FROM 1200' TO 25'. TOC @ 336'. PERFORATE AT 300'. RUN TBG TO 1220' & CIRCULATE CMT TO SURFACE WITH 85 SX CMT. CIRCULATE CMT TO SURFACE UP THE 4 1/2" X 8 5/8" ANNULUS FROM 300' WITH 55 SX CMT. TOOH WITH TBG & TOP OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2744	2760		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

*Ken Jehlik*  
(TECHNICIAN)

12/17/14 ckm

RECEIVED  
DEC 10 2014  
KCC DODGE CITY

KCC WICHITA  
DEC 12 2014  
RECEIVED

*SP*