

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-10072-00-00
Spot: NESW Sec/Twnshp/Rge: 26-23S-41W
1932 feet from S Section Line, 3308 feet from E Section Line
Lease Name: HCU Well #: 2631
County: HAMILTON Total Vertical Depth: 2463 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1000		
PROD	4.5	2463	0	WITH 100 SX CMT
SURF	8.625	100		WITH 150 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/24/2014 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JAVIER Company: ORR ENTERPRISES, INC. Phone: (620) 356-6961

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/25/2014 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

11/24/14: ATTEMPT TO RELEASE PACKER ON 2 7/8" TBG. COULD NOT. CUT TBG AT 2290'. NOT FREE. CUT TBG AT 1970'. COULD NOT PULL. WIRELINE LOCATOR INDICATES A POSSIBLE PACKER AT 1501-1506'. OPERATOR HAS NO RECORDS ON THIS WELL OTHER THAN A PACKER IS SET IN THE WELL ISOLATING A CASING LEAK. PUMP 50 SX CMT WITH 80# HULLS IN THE LAST 20 SX VIA 2 7/8" TBG TO 2438'. DISPLACE CMT TO 1200'. CUT TBG AT 1102'. TBG CAME FREE. 11/25/14: SET CIBP @ 1000'. ATTEMPT TO TEST 4 1/2" CASING. WOULD NOT HOLD PRESSURE. PERFORATE 4 HOLES AT 975'. RUN TBG & PACKER TO 600'. ATTEMPT TO LOAD ANNULUS. COULD NOT. HAVE HOLE IN 4 1/2" ABOVE PACKER. PUMP 50 SX CMT WITH 40# HULLS IN THE LAST 20 SX VIA TBG. DISPLACE CMT TO 750' @ 500#, LEAVING 15 SX CMT INSIDE THE CASING & 35 SX CMT OUT THE PERFS. PERFORATE 4 HOLES AT 300'. RUN TBG & PACKER TO 180'. CIRCULATE CMT TO SURFACE UP THE 4 1/2" X 8 5/8" ANNULUS WITH 140 SX CMT WHILE LEAVING 120' OF CMT INSIDE THE 4 1/2" CASING. RELEASE PACKER & PULL TBG TO 90' & CIRCULATE CMT TO SURFACE UP THE 4 1/2" CASING WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2428	2438		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

12/17/14 CCM

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

KCC WICHITA

DEC 12 2014

RECEIVED

RECEIVED

DEC - 3 2014

KCC DODGE CITY