

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20085-00-00  
Spot: NENE Sec/Twnshp/Rge: 31-22S-41W  
660 feet from N Section Line, 660 feet from E Section Line  
Lease Name: HCU Well #: 3121  
County: HAMILTON Total Vertical Depth: 2640 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2548		
PROD	4.5	2636	0	WITH 450 SX CMT
SURF	8.625	359		WITH 250 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/17/2014 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: JAVIER Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/18/2014 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2548'. PUMP 40 SX CMT FROM 2537' TO 1940'. RUN BOND LOG FROM 1000' TO 85'. TOC @ 750'. PERFORATE 4 HOLES AT 400'. RUN TBG TO 1150' & CIRCULATE CMT TO SURFACE IN THE 4 1/2" CASING WITH 85 SX CMT. CIRCULATE THE ANNULUS FULL OF CMT FROM 400' TO 0' WITH 75 SX CMT. TOP OFF 4 1/2" CASING WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2593	2610		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik  
(TECHNICIAN)

12/17/14 CKM

RECEIVED

DEC - 3 2014

KCC DODGE CITY

KCC WICHITA

DEC 12 2014

RECEIVED