

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20449-00-01
Spot: SWSWNENW Sec/Twnshp/Rge: 25-22S-42W
3966 feet from S Section Line, 3819 feet from E Section Line
Lease Name: HCU Well #: 2522-B
County: HAMILTON Total Vertical Depth: 2700 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2500		
PROD	4.5	2700	0	WITH 800 SX CMT
SURF	8.625	354		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/02/2014 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: GILBERTO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2500' WITH 30 SX CMT. FILL WITH CMT FROM 1250' TO 0'. FILL BACKSIDE WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 12/02/2014 8:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

CIBP @ 2500'. PUMP 35 SX CMT PLUG AT 2469' TO 1989'. PULL TBG TO 1250' & CIRCULATE CMT TO SURFACE WITH 90 SX CMT. TOO H WITH TBG & TOP OFF WITH 5 SX CMT. PUMP 15 SX CMT DOWN THE ANNULUS TO 300#.

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
KCC WICHITA (TECHNICIAN)

12/17/14 ccm

RECEIVED
DEC 10 2014
KCC DODGE CITY

DEC 12 2014
RECEIVED

ST