

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20466-00-00  
Spot: NE Sec/Twnshp/Rge: 25-22S-42W  
3968 feet from S Section Line, 1315 feet from E Section Line  
Lease Name: HCU Well #: 2522-C  
County: HAMILTON Total Vertical Depth: 2730 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2543		
PROD	4.5	2730	0	WITH 700 SX CMT
SURF	8.625	373		WITH 230 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/01/2014 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: GILBERTO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/01/2014 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2543'. SPOT 35 SX CMT FROM 2512' TO 2031' THROUGH TBG. FULL CIRCULATION. PULL TO 1250' & CIRCULATE CMT TO SURFACE WITH 90 SX CMT. TOOH WITH TBG & TOP OFF 4 1/2" CASING WITH 5 SX CMT. PUMP 5 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
2593	2679		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Ken Jehlik (TECHNICIAN)  
KCC WICHITA

12/1/14 cpm

RECEIVED  
DEC - 4 2014  
KCC DODGE CITY

DEC 12 2014  
RECEIVED