

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-24269-00-00
Spot: SWNWNENW Sec/Twnshp/Rge: 17-8S-17W
360 feet from N Section Line, 1543 feet from W Section Line
Lease Name: SCHINDLER Well #: 1W
County: ROOKS Total Vertical Depth: 3370 feet

Operator License No.: 34272
Op Name: OUTLAW WELL SERVICE LLC
Address: 1408 WEST 42ND
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 1258 | | |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/28/2014 12:00 AM
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC
Proposal Rcvd. from: TERRY Company: OUTLAW WELL SERVICE LLC Phone: (785) 303-8005

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY Witness Type: NONE
Date/Time Plugging Completed: 11/28/2014 11:00 AM KCC Agent: CHRIS NEELEY

Actual Plugging Report:

1st plug @3271 w/50 sx
2nd plug @1300 w/50 sx
3rd plug @690 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: GLOBAL

Plugged through: DP

District: 04

Signed Chris Neeley 12/17/14 ckm
(TECHNICIAN) CM

KCC WICHITA

DEC 16 2014

RECEIVED

DEC 8 2014