

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-20041-00-00  
Spot: SESW Sec/Twnshp/Rge: 1-17S-29W  
663 feet from S Section Line, 3314 feet from E Section Line  
Lease Name: TERWILLIGER Well #: 1  
County: LANE Total Vertical Depth: 4600 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2200		
PROD	5.5	4598	0	WITH 275 SX CMT
SURF	8.625	248		WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/24/2014 10:30 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIEK FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: SQUEEZE PERFS WITH 25 SX CMT & 100# HULLS. RUN BOND TO 2300' TO DETERMINE TOC. RUN TBG TO 2200' & CIRCULATE CMT. PULL TBG & TOP OFF.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/24/2014 12:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4200' & SPOT 50 SX CMT & 200# HULLS. COULDN'T LOAD. SET CIBP @ 2200' & LOADED HOLE. RUN BOND LOG & FOUND CMT TO SURFACE. RUN TBG TO 2168' & PUMPED 210 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 35 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4309	4319		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

12/17/14 CKM

District: 01

Signed Michael Maier (TECHNICIAN)

RECEIVED  
DEC - 5 2014  
KCC DODGE CITY

KCC WICHITA  
DEC 12 2014  
RECEIVED

*Handwritten initials*