

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-00309-00-00
Spot: NW Sec/Twnshp/Rge: 14-32S-39W
1300 feet from N Section Line, 1320 feet from W Section Line
Lease Name: YOUNGREN Well #: 1-14
County: STEVENS Total Vertical Depth: 2648 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N. O CONNOR BLVD., SUITE 200
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		800		
CIBP		1806		WITH 60 SX CMT
PROD 7		2396	0	WITH 800 SX CMT
SURF	10.75	510		WITH 325 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/20/2014 12:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: CIBP @ 1806' WITH 60 SX CMT. RUN CBL, TOC @ 90'. RUN TBG TO 700' CMT TO 0'. FILL UP BACKSIDE TO 500 PSI.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 11/20/2014 3:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

EXISTING CIBP @ 1806' WITH 60 SX CMT. SET CIBP @ 800'. RUN BOND LOG. FOUND TOC @ 90'. RTIH TO 700' CIRCULATE 135 SX CMT TO 0'. PUMP DOWN 7" X 10 3/4" ANNULUS WITH 25 SX CMT TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2554	2648		
2411	2480		
2389	2410		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED

DEC - 4 2014

KCC DODGE CITY

Signed

Kenny Sullivan

Received (TECHNICIAN)
KANSAS CORPORATION COMMISSION

DEC 11 2014

CONSERVATION DIVISION
WICHITA, KS

12/17/14 CKM

Form CP-2/3