

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-00015-00-01  
Spot: S2SESW Sec/Twnshp/Rge: 28-29S-17W  
352 feet from S Section Line, 3244 feet from E Section Line  
Lease Name: BARSTOW Well #: 1  
County: KIOWA Total Vertical Depth: 4925 feet

Operator License No.: 5893  
Op Name: PRATT WELL SERVICE, INC.  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4810		WITH 2 SX CMT
PROD	5.5	4920	0	WITH 200 SX CMT
SURF	8.625	350		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/01/2014 12:00 PM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: CIBP @ 4810' WITH 2 SX CMT. PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: NONE  
Date/Time Plugging Completed: 12/01/2014 7:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

CIBP @ 4810' WITH 2 SX CMT. PERFORATED AT 1060' & PUMPED 55 SX CMT.  
PERFORATED AT 380' & PUMPED 120 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4861	4873		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

12/17/14 CKM

District: 01

Signed Larry Harris  
(TECHNICIAN)

RECEIVED  
DEC - 5 2014  
KCC DODGE CITY

KCC WICHITA  
DEC 12 2014  
RECEIVED

*Handwritten initials*