

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-20924-00-00
Spot: SWSW Sec/Twnshp/Rge: 28-32S-10W
660 feet from S Section Line, 4620 feet from E Section Line
Lease Name: MCGUIRE Well #: VI
County: BARBER Total Vertical Depth: 4460 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4459	2310	WITH 150 SX CMT
SURF	8.625	292		WITH 225 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 12/03/2014 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 12/03/2014 6:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 30 SX CMT & 200# HULLS AT 4370'. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4436	4442		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed

Michael Maier

(TECHNICIAN)
KCC WICHITA

DEC 12 2014
RECEIVED

RECEIVED
DEC - 5 2014
KCC DODGE CITY

12/17/14 CCM

SR