

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-21963-00-00
Spot: NWNENWNE Sec/Twnshp/Rge: 26-24S-11W
315 feet from N Section Line, 1962 feet from E Section Line
Lease Name: PAULSEN Well #: 1
County: STAFFORD Total Vertical Depth: 3905 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3903	2110	WITH 100 SX CMT
SURF	8.625	247		WITH 150 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/03/2014 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO PERFS & CAP WITH 5 SX CMT. PLUG AT 570' WITH 50 SX CMT. CIRCULATE TO SURFACE FROM 270'.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2014 12:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SAND BACK AT 3740' WITH 4 SX. SAND BACK TO 3388' WITH 5 SX CMT. 1ST PLUG AT 560' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 260' WITH 75 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3806	3812		
3442	3445		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY COPELAND CEMENT.

Plugged through: CSG

District: 01

Signed

[Signature]

(TECHNICIAN)

RECEIVED

DEC - 5 2014

KCC DODGE CITY

KCC WICHITA

DEC 12 2014

RECEIVED

Form CP-2/3