

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,173

LEASE NAME Reschke "A" #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION NW NW SE

SEC. 9 TWP. 27S RGE. 14W (E) or (W)

COUNTY Pratt

Date Well Completed \_\_\_\_\_

Plugging Commenced 8 15/84

Plugging Completed 8/20/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F & M Oil Co., Inc.

ADDRESS 422 Union Center, Wichita, Ks. 67202

PHONE # (316) 262-2636 OPERATORS LICENSE NO. 5313

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	328'	none
				4 1/2"	4475'	2385'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3880' & 4 sacks cement, Shot pipe at 3028' 2832', 2617', and 2385'. Pulled 59 joints of pipe. Plugged well with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, & 150 sacks cement.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 21st day of August, 1984



Irene Hoover  
Notary Public

My Commission expires: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

AUG 22 1984

CONSERVATION DIVISION  
Wichita, Kansas


CONTRACTOR'S WELL LOG

OPERATOR:	F & M OIL CO., INC.
CONTRACTOR:	Union Drilling Co., Inc.
LEASE NAME:	Reschke "A" #1
LOCATION:	NW NW SE Section 9-27S-14W Pratt County, Kansas
COMMENCED:	August 10, 1982
COMPLETED:	August 19, 1982

0	930	Redbed & shale	Set 8-5/8" @ 328' w/275 sxs common
930	3256	Shale	cement 2% gel, 3% CC
3256	3499	Shale & lime	
3499	4057	Lime & shale	
4057	4670	Lime	
4670		RTD	

We certify that the above foregoing is a true and correct copy of the log on the Reschke "A" #1 , NW NW SE Section 19-27S-14W, Pratt County, Kansas.

Union Drilling Co., Inc.

  
R. D. Messinger

STATE OF KANSAS     )  
   ) SS  
 COUNTY OF SEDGWICK )

Subscribed and sworn before me, a Notary Public in and for the aforesaid County and State as of this 26th day of August, 1982.

My appointment expires:  
12-24-84

  
Shirley A. Gallegos-Notary Public



RECEIVED  
STATE CORPORATION COMMISSION

AUG 02 1984

CONSERVATION DIVISION  
Wichita, Kansas