

JUN 29 1981  
6-29-81  
CONSERVATION DIVISION  
Wichita, Kansas



P.O. Box 18595 / Wichita, KS 67218

Wichita (316) 262-3071  
(316) 685-1401

Great Bend (316) 793-5285

Mobile (316) 672-5663  
Unit 2904

Fig #1 (316) 672-5663  
Unit 2905

### DRILLERS' WELL LOG

Jones #1-6  
SE, SE, SW, Section 6, TWP. 27S, R14W  
Pratt County, Kansas

Commenced: 6-9-81

Completed: 6-23-81

OPERATOR: Texas Energies, Inc.

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	250	Sand	Spudded at 11:30 P.M. 6-9-81
250	370	Redbed	Ran 9 jts. of 8 5/8" csg 362' set @ 370'
370	1587	Sand & Shale	Cement w/130 Sks Howcolite & 130/sks
1587	4710	Shale & Lime	Common 2% Gel 3% CC
			Job complete at 8:45 A.M. 6-10-81
			Total Depth of well 4710 ft.
			D.A. plugged well 1st plug at 620'
			Cemented w/60 sks 50/50 Pos-Mix 4% Gel
			3% CC 2nd plug at 360' cemented w/40
			sks 50/50 Pos-Mix 4% Gel 3% CC
			Bridge plug @ 40' w/10 sks
			10/sks in rat hole 2 sks water well
			Cement = 122 sks 50/50 Pos-Mix 4% Gel
			3% CC
			Plug set & job complete at 4:30 P.M.
			6-23-81

STATE OF KANSAS )  
 ) ss.  
COUNTY OF SEDGWICK)

I, the undersigend, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.


LANDMARK ENERGY CORPORATION


BY: 

R. L. Smith, President

MY COMMISSION EXPIRES:

6-18-83



  
Judy Jo Peterson