

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

PRATT County. Sec. 28 Twp. 27 Rge. 14 ~~EX~~ (W)

Location as "NE/CNWxSWx" or footage from lines. NW SE SE
Lease Owner. El Dorado Refining Company
Lease Name. Vanatta Well No. 1
Office Address. 306 Koch Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 1, 19 53
Application for plugging filed July 31, 19 53
Application for plugging approved July 31, 19 53
Plugging commenced July 31, 19 53
Plugging completed July 31, 19 53
Reason for abandonment of well or producing formation Dry Hole.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 4655 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	416'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud. Pushed bottom plug to 300'. Cemented with 20 sacks of cement through the drill pipe. Filled hole within 35' of surface. Set plug, and cemented with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
Address P. O. Box 218, Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
Rollin Mead (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Rollin Mead
P. O. Box 218 - Sterling, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of August, 19 53

My commission expires Sept. 17, 1953

[Signature]
Notary Public.

24-7368-5 3-53-20M RECEIVED STATE CORPORATION COMMISSION

AUG - 5 1953
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC 28 27 14
BOOK PAGE 119 LINE 8

WELL LOG ----- #1 VANATTA

Location: NW SE SE Section 28-27-14W, Pratt County, Kansas

Owner: El Dorado Refining Company

Rotary Drilling Contractor: Sterling Drilling Company

Commenced: July 11, 1953

Completed: August 1, 1953

Total: 4655'

LOG

200-416	Clay and Sand
416-855	Redbed
855-1330	Redbed, Shale and Shells
1330-1675	Shale and Shells
1675-1930	Lime and Shale
1930-2550	Lime
2550-3195	Lime and Shale
3195-3590	Lime
3590-3875	Lime and Shale
3875-3896	Brown Lime
3896-3935	K.G. Lime
3935-4400	Lime
4400-4425	Lime and Shale
4425-4465	Lime, Sand, Shale and Chert
4465-4520	Lime
4520-4555	Lime and Shale
4555-4600	Lime
4600-4642	Lime and Shale
4642-4655	Arbuckle Lime

CASING RECORD

416' 8-5/8" Surface Pipe set at 416'. 300 sacks bulk cement, and 5 sacks calcium chloride.

PRODUCTION: Dry and Abandoned

RECEIVED
 CONSERVATION COMMISSION
 AUG - 5 1953
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 28 T 27 R 14W
 BOOK PAGE 119 LINE 8