

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 23 Twp. 27 Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines C SE/4 NW/4  
Lease Owner Braden Drilling, Inc.  
Lease Name Krusemark Well No. 1  
Office Address 1206 Union National Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed July 9 19 61  
Application for plugging filed July 9 19 61  
Application for plugging approved July 9 19 61  
Plugging commenced July 9 19 61  
Plugging completed July 9 19 61  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation Depth to top Bottom Total Depth of Well 4690 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	300	8 5/8	300	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 290' and cemented with 20 sacks cement. Filled hole with heavy mud.  
Set plug at 30' and cemented with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 14 1961  
CONSERVATION DIVISION  
WICHITA, KANSAS  
07-14-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Braden Drilling, Inc.  
Address 1206 Union National Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
F. M. Callaway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
1206 Union National Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of July, 19 61

My commission expires March 21, 1962

[Signature] Notary Public.

INVOICED  
DATE 7/18/61  
INV. NO. 3383-W

DRILLER'S LOG

Braden Drilling, Inc. et al  
 KRUSEMARK #1  
 C SE/4 NW/4 Sec. 23-27S-14W  
 Pratt County, Kansas

Commenced: June 24, 1961

Completed: July 9, 1961

Set 8 5/8" at 300' and cemented  
 with 300 sacks cement.

Sand and shale	300 feet
Shale and redbed sand	900
Redbed, shale & shells	1485
Shale and shells	1940
Lime	2302
Lime and shale	2410
Lime	2525
Lime and shale	2755
Lime	2998
Lime and shale	3915
Lime	4270
Lime and shale	4335
Lime and chert	4430
Chert	4448
Lime and Chert	4510
Chert	4538
Chert and shale	4543
Shale and sand	4638
Arbuckle Lime	4678
Lime	4690 Total depth

I hereby certify that this is a true and correct log of the above captioned well, as shown by the daily drilling reports.

F. M. Callaway  
 F. M. Callaway

Subscribed and sworn to before me this 11th day of July, 1961.

My commission expires March 21, 1962.

Helen Schultz  
 Helen Schultz, Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 14 1961  
 CONSERVATION DIVISION  
 Wichita, Kansas