

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-20673-DD-20

LEASE NAME Newby

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-14

2310 Ft. from S Section Line

2440 Ft. from E Section Line

SEC. 14 TWP. 27S RGE. 15 (E) or (W)

COUNTY Pratt

LEASE OPERATOR Trans Pacific Oil Corporation

ADDRESS 100 N. Main Suite 1000, Wichita, Kansas 67202

PHONE (316) 262-3596 OPERATORS LICENSE NO. 9408

Date Well Completed 02/22-1980

Plugging Commenced 04-25-96

Plugging Completed 04-26-96

Character of Well oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04-25-96 (date)

by Steve Durrant (KCC District Agent's Name)

is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation Cherokee Sand Depth to top 4430' Bottom 4434 r.c. 4790'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface			8 5/8"	336'	0
	Production			4 1/2"	4715'	2273'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from feet to feet each set
Bottom plug; sanded off to 4380' 4 sks of cement. Allied mixed 300 lbs. of Cotton seed hulls, 10 sks of gel, 50 sks of cement 10 sks of gel 100 lbs. of hulls. 100 sks of cement and 8 5/8" plug.
Maximum pressure 300 lbs. ISIP 100 lbs.

Name of Plugging Contractor D.S.& W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Trans Pacific Oil Corporation

STATE OF Kansas COUNTY OF Barton, ss.

Joseph F. Strube

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same to be true and correct, so help me God.

KANSAS CORPORATION COMMISSION

(Signature) Joseph F. Strube

(Address) P.O. Box 231, Claflin, Kansas 67525

05-06-96
MAY 06 1996


SUBSCRIBED AND SWORN TO before me this 03 day of May, 19 96

CONSERVATION DIVISION
WICHITA, KS

Bonnie L. Connell
Notary Public

My Commission Expires: 04-08-97

USE ONLY ONE SIDE OF EACH FORM



Form CP-4
Revised 05-88

RECEIVED
 KANSAS CORP COMM GABBERT-JONES, INC.
 1996 MAR 19 A 11: 59 WICHITA, KANSAS
 DRILLERS' WELL LOG

Newby #1-14
 C-S/2-N/2 Sec 14-27S-15W
 Pratt County Kansas

Commenced: 10-30-79

Completed: 11-12-79

OPERATOR: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	342	Sand-Shale	Ran 8 jts of 28# 8 5/8" csg
342	1758	Shale-Redbed	set @ 336' Cemented w/
1758	2015	Shale-Shells	100 600 sbs 65/35 Posmix 6% Gal
2015	2416	Shale-Lime	3% CC - 75 sbs Class A
2416	2678	Shale	3% CC PD @ 2:15 a.m. 10-31-79
2678	2869	Shale-Lime	Hole in 8 5/8" csg Cemented
2869	3010	Lime-Shale	w/150 sbs Class A 2 % Gal
3010	3045	Shale-Lime	3% CC Job Complete @ 6:15 p.m.
3045	3355	Lime-Shale	10-31-79
3355	3550	Shale-Lime	
3550	3900	Lime-Shale	
3900	4050	Shale-Lime	Ran 113 jts of 10 1/2" 4 1/2" csg
4050	4305	Lime-Shale	set @ 4715' Cemented w/
4305	4400	Shale-Lime	150 sbs Common 10% Salt
4400	4790	Lime	w/Latex added Last 70 sbs
			PD @ 6:40 a.m. 11-12-79

4790 - TD

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Driller' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 16th day of November, 1979.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

