

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County. Sec. 14 Twp. 27S Rge. (E) 15 (W)

Location as "NE/CNW%SW%" or footage from lines SE SW SW
Lease Owner Braden-Deem, Inc.
Lease Name Irwin Well No. 1
Office Address 200 E. First, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 6/18/ 19 60
Application for plugging filed Dec. 18 19 73
Application for plugging approved Dec. 20 19 73
Plugging commenced March 6 19 74
Plugging completed March 19 19 74
Reason for abandonment of well or producing formation



If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4575 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	355	none
				5-1/2	4528	2372

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand from 4500 to 4400'
Dump 5 sacks cement with dump bailer
Cement from 4400 to 4365'
Ripped pipe at 2800 - 2670 - 2500 - 2370'
Built wood bridge at 200'
Rock from 200 to 190'
3 yards of Ready-Mix

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1974

03-26-74

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Clarke Corp License No. 583
Address Box 187, Medicine Lodge, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Doy C. Deem (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
200 E. First, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of March, 1974

My commission expires March 21, 1978

[Signature] Notary Public.

DRILLER'S LOG

Braden Drilling, Inc. et al

Commenced: February 17, 1960

IRWIN #1
SE SW SW Sec. 14-27S-15W
Pratt County, Kansas

Completed: March 5, 1960

Set 3 5/8" at 354' and cemented
with 350 sacks cement.

Set 5 1/2" at 4528' and cemented
with 100 sacks cement.

Sand and shale	210 ft.
Shale and shells	680
Shale	980
Anhydrite	1000
Shale and shells	1630
Lime and shale	2050
Lime	2785
Shale and Lime	3470
Lime	3700
Lime and shale	3975
Lime.	4335
Lime and shale	4398
Lime	4575 T.D.

RECEIVED
STATE CORPORATION COMMISSION
JAN 9 1973
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct log of the above captioned well, as shown by the daily drilling reports.

F. M. Callaway

Subscribed and sworn to before me this 21st day of December, 1961.

My commission expires March 21, 1962

Helen Schultz, Notary Public