


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 13 Twp. 27S Rge. 15W (E) W (W)
Location as "NE/CNWxSWx" or footage from lines SW SW SW
Lease Owner Anschutz Drilling Co., Inc.
Lease Name Jones Well No. 1
Office Address 709 Union National Bank Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 11, 1955
Application for plugging filed January 11, 1955
Application for plugging approved January 11, 1955
Plugging commenced January 11, 1955
Plugging completed January 11, 1955
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4785' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	323'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug set at 300' with 20 sacks cement displaced through pipe.
Top plug set at 35' with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor _____
Address _____

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. G. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. G. Koelling
709 Union National Bank Building
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of January, 19 55
Charlonne Baehner
Notary Public.

My commission expires July 28, 1958



01-15-55

DRILLER'S LOG

Anschutz Drilling Co., Inc.

Jones #1

SW SW SW 13-27S-15W

Pratt County, Kansas

<u>TO</u>	<u>FROM</u>	
0	250	Sand
250	426	Red Bed
426	950	Red Bed & Sand Stks.
950	980	Anhydrite
980	1705	Shale & Shells
1705	1960	Salt, Shale & Lime
1960	2065	Lime & Shale
2065	2160	Lime
2160	2380	Lime & Shale
2380	2790	Shale & Lime
2790	3025	Lime & Shale
3025	3370	Shale & Lime
3370	3561	Lime
3561	3645	Shale & Lime
3645	3826	Lime & Shale
3826	3975	Shale & Lime
3975	4270	Lime
4270	4375	Lime & Shale
4375	4400	Lime
4400	4429	Shale & Sand
4429	4459	Chert, Shale & Lime
4459	4505	Shale & Sand
4505	4527	Chert, Lime & Shale
4527	4570	Lime
4570	4613	Lime, Shale & Sand
4613	4658	Lime & Shale
4658	4705	Shale & Sand
4705	4735	Shale & Lime
4735	4785	Arbuckle
	4785	ROTARY TOTAL DEPTH

COMMENCED: 12-23-54
COMPLETED: 1-11-55

CASING RECORD:

Set 223' of 8 5/8" surface casing with 225 sacks cement.

D & A

STATE OF KANSAS)

COUNTY OF SEDGWICK)

SS

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Jones #1 located SW SW, SW in Section 13-27S-15W, Pratt County, Kansas.

ANSCHUTZ DRILLING CO., INC.

PLUGGING
 FILE SEC 13-27-15W
 BOOK PAGE 90 LINE 36

BY:

E. G. Koelling
E. G. Koelling

Subscribed and sworn to before me this 14th day of January, 1955.

Charlene Barlow
Notary Public

My Commission Expires: July 28, 1958.